


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County, Sec. 3 Twp. 22S Rge. 24W ~~XXX~~  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

C - NW SW  
Lease Owner Twin Western Resources, Inc.  
Lease Name Bobbi Well No. 1  
Office Address 920 Union Cntr., Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed May 28, 1978  
Application for plugging filed Verbal Application 19\_\_  
Application for plugging approved Verbal Approval 19\_\_  
Plugging commenced May 28, 1978  
Plugging completed May 28, 1978  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,740  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	604'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,740 ft. (rotary total depth) to 1,000 ft. Set plug at 1,000 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 1,000 ft. to 600 ft. Set plug at 600 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 600 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 $\frac{1}{2}$  inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.  
Box 31, Russell, Kansas 67665

JUN 05 1978

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent

~~XXXXXXXXXXXXXXXXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)



SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1978

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires June 30, 1978

KANSAS DRILLERS LOG

COMPANY Twin Western Resources, Inc.

SEC. 3 T. 22S R. 24W

FARM Bobbi

NO. 1

LOC. C - NW 64

COUNTY Hodgeman

ROTARY TOTAL DEPTH 4,740'  
COMM. May 16, 1978  
CONTRACTOR H-30, Inc.  
ISSUED June 3, 1978

COMP. May 23, 1978

CASING

10 3/4"  
8 5/8" Set at 604' cemented w/300 sxs cement  
5 1/2"  
4 1/2"

ELEVATION 2,467 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	610'
Shale and Shells	1,106'
Shale	1,170'
Sand	1,385'
Shale and Sand	1,650'
Shale	1,656'
Anhydrite	1,729'
Shale and Lime	2,530'
Lime and Shale	2,651'
Shale and Lime	2,821'
Lime and Shale	3,243'
Shale and Lime	3,496'
Lime and Shale	4,398'
Lime	4,740'
Rotary Total Depth	4,740'

RECORDED  
STATE OF KANSAS  
JUN 15 1978

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 2nd day of June, 1978.

WILLISON  
NOTARY

Elsie Willison  
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978