


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Rice County. Sec. 11 Twp. 21 Rge. 9 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE NW NW  
Lease Owner Lee Phillips Oil Company  
Lease Name Read Well No. 1  
Office Address 1407 Union Nat'l Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 2, 1959  
Application for plugging filed " 2, 1959  
Application for plugging approved " " (verbally) 1959  
Plugging commenced " " 1959  
Plugging completed " " 1959  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 337 1/2 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	293'	8 5/8"	293'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from total depth to 280' with plug and 20 sacks of cement at this point. Filled with heavy mud to 40' with plug and 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1959  
05-26-59  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Harms-Burt Drilling Company  
Address P. O. Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
P. O. Box 184, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of April, 1959

Mary E. Van Pelt  
Notary Public.

My commission expires Jan. 20, 1962

PLUGGING  
FILE SEC. 11 T. 21 R. 9 W  
BOOK PAGE 41 LINE 13

DRILLERS LOG

Company: Lee Phillips Oil Co.  
 Farm: Read #1  
 Commenced: March 19, 1959

SE NW NW Section 11-21-9W  
 Rice County, Kansas  
 Completed: April 2, 1959

Elevation: 1673 KB

0 - 160	sand
160 - 293	red bed
293 - 400	shale & red bed
400 - 620	shale & sand
620 - 1000	shale & shells
1000 - 1100	shale & lime
1100 - 1750	lime & shale
1750 - 2360	shale & lime
2360 - 2400	lime
2400 - 2463	shale & lime
2463 - 2756	lime
2756 - 2762	Heebner shale
2762 - 2766	Lime
2766 - 2890	shale
2890 - 3314	lime
3314 - 3350	Viola Ls
3350 - 3374	Simpson
3374	Total Depth

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 26 1959

CONSERVATION DIVISION  
 Wichita, Kansas

Set 293 feet of 8 5/8" surface pipe. Cemented with 300 sacks of posmix with 2% calcium chloride.

Tops:

Heebner - 2756
Br. Lime - 2890
Lansing K.C. - 2919
Viola - 3314
Simpson - 3350

Drill Stem Tests: #1 3361-3374 Open 1 hour. Shut in 20 min. Recovered 1900' water - BHP 845#

Dry, plugged and abandoned.

A F F I D A V I T

STATE OF KANSAS )  
 )SS.  
 COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Subscribed and sworn to before me this 9 day of April, 1959.

Mary E. Van Pelt  
 Notary Public

My commission expires January 20, 1962.

