


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rice County, Sec. 28 Twp. 21S Rge. 9 (W)  
Location as "NE/CNW/SW" or footage from lines NW NE NW  
Lease Owner Jay-Bee Oil Company, Inc.  
Lease Name Wellman Well No. 1  
Office Address 515 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 16, 1966  
Application for plugging filed December 16, 1966  
Application for plugging approved December 16, 1966  
Plugging commenced December 16, 1966  
Plugging completed December 16, 1966  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 10  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, McPherson, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3575 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug from 3400 feet to 3300 feet with 55 sacks cement. Mudded up with heavy mud to 260 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 50 feet followed by wooden plug, 1 sack hulls and 20 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

01-03-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF BUTLER ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
505 Union Center, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 28th day of December, 1966

My commission expires April 30, 1967 Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Jay-Bee Oil Company, Inc. DRILLING COMMENCED: December 9, 1966  
515 Union Center  
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: December 16, 1966  
509 Union Center  
Wichita, Kansas

CASING RECORD: 7 Jts. 270' 8-5/8" cemented with 250 sacks  
LOCATION: Wellman No. 1  
NW NE NW  
Section 28-21S-9W  
Rice County, Kansas

-----

0 - 60	Sand
60 - 253	Red bed
253 - 270	Anhydrite
270 - 322	Red bed
322 - 720	Red bed & sand
720 - 1158	Shale & shells
1158 - 2040	Lime & shale
2040 - 2255	Shale & lime
2255 - 2415	Lime & shale streaks
2415 - 2775	Lime & shale
2775 - 2805	Lime
2805 - 2939	Lime & shale
2939 - 2965	Brown lime & shale
2965 - 3476	Lime
3476 - 3493	Lime, shale & sand
3493 - 3525	Sand & sandy shale
3525 - 3575	Lime
3575	Rotary Total Depth

RECEIVED  
STATE OF KANSAS  
JAN 8 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves President

STATE OF KANSAS )  
                  ) SS:  
BUTLER COUNTY )

Subscribed and sworn to before me, a Notary Public, this 28th of December, 1966.

Betty Brandt  
Betty Brandt Notary Public

My commission expires:  
April 30, 1967