

15-135-01005-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Neos County, Sec 29 Twp 17 Rge 22 (E) (W)

Location as "NE/CNW/SW" or footage from lines 6 S. 17 N.

Lease Owner Full Drilling Co. Inc.

Lease Name Favlu Well No. 1

Office Address 1625 Plaza Bldg. Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.

Date well completed 2-2-63 19

Application for plugging filed 2-2-63 19

Application for plugging approved 2-2-63 19

Plugging commenced 4:00 p.m. 2-2-63 19

Plugging completed 5:00 p.m. 2-2-63 19

Reason for abandonment of well or producing formation _____

Non productive.

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

X	#4		

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1375' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well Plugged through drill pipe with pump truck. Plug put at 60' with 20 sacks cement, 2nd. Plug put at 240' with 20 sacks cement. Third put at 40' with 10 sacks. Two sacks cement put in rat hole plugging same.

FEB 11 1963
STATE CORPORATION COMMISSION

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe cementing co.

Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of February, 1963

B. H. Satter
Notary Public.

My commission expires OCTOBER 16, 1965



ROTARY DRILLING LOG

15-135-01005-00-00

COMPANY: **Hall Drilling Company**
 1625 Wichita Plaza
 Wichita, Kansas
 LOCATION: **C SW NE 28-178-22W, Ness County, Kansas**
 Well No. 1

Rotary Drilling Commenced 1-20-63

Rotary Drilling Completed 2-2-63

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (11 jts) 8 3/8" surface casing set at 263', cemented with 175 sacks cement. Circulated. Completed 3:30 P.M., January 20, 1963. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

30	Top Soil - Clay	<u>Circ. For Samples</u>
80	Clay & Shale	4260
110	Shale & Shells	4270
335	Blue Shale	4275
370	Sand	4285
730	Shale & Shells	4295
800	Sand	
980	Red Beds - Shale	
1250	Sand	
1315	Red Beds	<u>Slope Tests</u>
1530	Red Bed and Shale	2200
1560	Anhydrite	2700
1970	Shale & Shells	3200
2165	Lime & Shale	3700
2430	Lime	
2555	Lime & Shale	<u>S. L. M.</u>
2790	Lime	3307
2985	Lime & Shale	3651
3096	Shale & Lime Shells	3940
3270	Lime & Shale	
3383	Lime & Shale, Sandy	
3705	Lime & Shale	
4000	Lime	
4065	Lime & Shale	
4153	Lime	
4205	Lime & Shale	
4255	Lime	
4275	Lime - Chert	
4322	Mississippian	
4348	Mississippi Chert	
4375	Chert - KD	

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 11 1963
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 7th day of February, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
 Notary Public
 Maxine Blackman