


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 31 Twp. 17S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner Mull Drilling Company, Inc.
Lease Name FRENCH Well No. 1
Office Address 1625 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 21 1965
Application for plugging filed August 21 1965
Application for plugging approved August 21 1965
Plugging commenced August 21 1965
Plugging completed August 21 1965
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.
If a producing well is abandoned, date of last production - - - - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4318 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278.42 1/2	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 540', spotted with 20 sacks cement, mud back to 220', set plug & hulls, spotted with 20 sacks cement, mud back to 40', set solid bridge with hulls & plug, capped with 10 sacks cement, 2 sacks in rathole. Plugging completed 10:30 a.m. 8-21-65.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 1965

My commission expires January 8, 1968
Shirley Keck Notary Public.

ROTARY DRILLING LOG

15-135-30072-00-00

Operator: Mull Drilling Company, Inc.
 #1 FRENCH
 C SE SW Section 31-17S-22W
 Ness County, Kansas

CONTRACTOR: Rains & Williamson
 Oil Co.

COMMENCED: 8-12-65
 COMPLETED: 8-21-65

REMARKS: Set 278.42½° of
 8-5/8" surface casing
 with 200 sacks GL3
 cement.

FORMATIONS:

Soil & Clay	40'
Shale	280'
Shale & Sand Streaks	550'
Shale & Shells	955'
Sand	1175'
Red Bed & Shale	1285'
Shale	1516'
Anhydrite	1557'
Shale & Shells	2220'
Shale & Lime	2405'
Lime	2975'
Lime & Shale	3715'
Lime	4318'
RTD (D&A)	4318'

RECEIVED
 STATE CORPORATION COMMISSION

SEP 1 1965

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the
 State of Kansas, County of Sedgwick, this 30th day of August, 1965.

My Commission Expires:
 January 8, 1968

Shirley Keck
 Shirley Keck, Notary Public