

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22028-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 20-17S-24W  
2295 feet from N Section Line, 651 feet from E Section Line  
Lease Name: SIDEBOTTOM Well #: 4  
County: NESS Total Vertical Depth: 4425 feet

Operator License No.: 31788  
Op Name: VEENKER RESOURCES, INC.  
Address: PO BOX 14339  
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4235		WITH 2 SX CMT
SURF	8.625	292		WITH 180 SX CMT
PROD	5.5	4424	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2012 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: MARK VEENKER Company: VEENKER RESOURCES Phone: (405) 751-1414

Proposed Plugging Method: TBG TO 2300' WITH 50 SX CMT & 200# HULLS. TEST & HOLD PRESSURE. PERFORATE @ 1100'. PUMP 80 SX CMT OVER CASING VOLUME & 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 03/19/2012 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4235' WITH 2 SX CMT. RUN TBG TO 2274' & PUMP 50 SX CMT WITH 200# HULLS. WAIT FOR CMT TO SET UP. PRESSURE TO 200# & HELD. PERFORATE @ 1100' & PUMP 200 SX CMT. HOOK UP TO BACKSIDE & PUMP 50 SX CMT. HELD AT 500 PSI.

Perfs:

Top	Bot	Thru	Comments
4356	4362		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Michael Maier*  
(TECHNICIAN)

RECEIVED

APR 10 2012

KCC DODGE CITY

RECEIVED

APR 16 2012

KCC WICHITA

4/30/12  
Form CP-2/3

*DMY*