

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20610-00-00
Spot: SESESW Sec/Twnshp/Rge: 4-17S-27W
294 feet from S Section Line, 2951 feet from E Section Line
Lease Name: KUEHN Well #: 5
County: LANE Total Vertical Depth: 4526 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	322		WITH 200 SX CMT
PROD	4.5	4500	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2012 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: JASON SHULAR Company: ABERCROMBIE Phone: (620) 793-8186

Proposed Plugging Method: PUMP 50 SX CMT WITH 300# HULLS W/2% CC. SPOT 20 SX CMT AT 2050'. PERFORATE AT 1300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2012 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4016' & PUMP 70 SX COMMON CMT W/2% CC & 300# HULLS. PULL TBG & WAIT 1 1/2 HOURS. TIE ONTO CASING & PRESSURED TO 300# & HELD. PERFORATE AT 1270'. TIED ONTO CASING & TOOK INJECTION RATE OF 2 BBL A MINUTE AT 500#. RUN TBG TO 2050' & SPOT 20 SX CMT. PULL TBG & TIED ONTO CASING WITH SWEDGE & PUMPED 210 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4486	4492		
3897	4159		

Remarks: USED COMMON CEMENT W/2% CC & 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
APR - 5 2012
KCC DODGE CITY

RECEIVED
APR 16 2012
KCC WICHITA
Form CP-2/3
4/30/12
BANK