

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21671-00-01
Spot: NESWSW Sec/Twnshp/Rge: 5-16S-27W
990 feet from S Section Line, 990 feet from W Section Line
Lease Name: USA Well #: 1
County: LANE Total Vertical Depth: 4460 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	269		WITH 205 SX CMT
DVT		1256		WITH 300 SX CMT
PROD	4.5	4440	0	WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2012 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4050' WITH 2 SX CMT. RUN TBG TO 2100' & CIRCULATE CMT TO SURFACE USING HULLS IN CMT. ATTEMPT TO PUMP CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2012 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****CASING LEAK APPROXIMATELY 1650'**. ATTEMPT TO RUN 3 3/4" BIT ON 2 3/8" TBG THROUGH TIGHT SPOT @ 1668'. WOULD NOT GO. ATTEMPT TO RUN TBG THROUGH TIGHT SPOT @ 1668'. STACKED OUT. ATTEMPT TO RUN TBG WITH 2 1/16" PILOT SWAGE ON BOTTOM STACKED OUT AT 1668'. ROTATED. NO SUCCESS. ATTEMPT TO CIRCULATE DOWN. COULD NOT. SUSPECT PARTED CASING IN THE CEDAR HILLS. SPOT 40 SX CMT AT 1668'. NO CIRCULATION. TOO H W/TBG & REMOVE 2 1/16" SWAGE. TIH TO 1367' & CIRCULATE HOLE FULL OF CMT WITH 175 SX CMT & 300# HULLS. TOO H W/TBG. TOP OFF 4 1/2" CASING WITH 15 SX CMT. STAYED FULL. PUMP 10 SX CMT DOWN THE ANNULUS. PRESSURE TO 400#.**

Perfs:


Top	Bot	Thru	Comments
4310	4332		
4102	4106		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS A NEAT CEMENT BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR - 3 2012
KCC DODGE CITY

RECEIVED
APR 16 2012
KCC WICHITA

Form CP-2/3

4/30/12

BWA