

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12891-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 22-22S-14W
2284 feet from S Section Line, 2353 feet from E Section Line
Lease Name: OSCAR WEST Well #: 701W
County: STAFFORD Total Vertical Depth: 3923 feet

Operator License No.: 33809
Op Name: BELPORT OIL, INC.
Address: 1443 S NORFOLK AVE
TULSA, OK 74120

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3460		
SURF	8.625	249		WITH 175 SX CMT
PROD	5.5	3720	0	WITH 75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2012 1:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: CHIP CAMPBELL Company: BELPORT OIL Phone: (918) 584-8989

Proposed Plugging Method: SET CIBP @ 3460' ON 2/8/08. 8/10/08: PUMPED 100 SX CMT AT 2002' INSIDE THE 5 1/2" CASING TO SEAL OFF CASING LEAKS. PRESSURE TESTED CASING ABOVE 1600' TO 300 PSIG. PERFORATE 5 1/2" AT 820'. PUMP CMT UNTIL CMT CIRCULATES TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2012 4:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFORATED 5 1/2" @ 820'. PUMPED 450 SX CMT DOWN 5 1/2" CASING CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3611	3619		
1600	2002		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
APR 13 2012
KCC DODGE CITY

RECEIVED
APR 16 2012
KCC WICHITA

Form CP-2/3

4/30/12