

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20790-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 9-27S-24W  
2217 feet from S Section Line, 2149 feet from E Section Line  
Lease Name: CHEYENNE Well #: 5-9  
County: FORD Total Vertical Depth: 5125 feet

Operator License No.: 31930  
Op Name: BLUE RIDGE PETROLEUM CORPORATI  
Address: PO BOX 1913  
ENID, OK 73702

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 8.625 | 424        |             |         |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2012 10:15 PM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: TIM FABRICIUS Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 1570' WITH 50 SX CMT. 2ND PLUG AT 820' WITH 80 SX CMT. 3RD PLUG AT 460' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 04/03/2012 12:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1570' WITH 50 SX CMT. 2ND PLUG AT 820' WITH 80 SX CMT. 3RD PLUG AT 460' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY

Plugged through: DP

District: 01

Signed Richard M Lacey  
(TECHNICIAN)

RECEIVED  
APR 13 2012  
KCC DODGE CITY

RECEIVED Form CP-2/3  
APR 16 2012 4/30/12

KCC WICHITA