

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21629-01-00
Spot: N2N2NWNW Sec/Twnshp/Rge: 20-31S-19W
191 feet from N Section Line, 685 feet from W Section Line
Lease Name: RUBY Well #: 1-20H
County: COMANCHE Total Vertical Depth: 1010 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		260		
SURF	9.625	260		WITH 760 SX CMT
COND	20	150		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 04/12/2012 12:00 PM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: TYLER MCCULLAR Company: SANDRIDGE EXPLORATION & PR Phone: (432) 290-8533

Proposed Plugging Method: SPOT 75 SX CMT AT 290'. CIRCULATE CMT TO SURFACE FROM 60' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 04/12/2012 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

HALLIBURTON ENERGY SERVICES PUMPED 2600 SX CMT INTO THE VOID UNDER THE SUBSTRUCTURE. SANDRIDGE DECIDED TO TRY TO DRILL THE WELL WITHOUT SKIDDING THE RIG. DRILLED THROUGH THE CMT & LOST CIRCULATION AGAIN. SET 9 5/8" @ 260' & PUMPED 360 SX CMT WITH NO CIRCULATION. TAGGED CMT AT 70' & ONE-INCHED CMT TO SURFACE WITH 400 SX CMT. LOST CIRCULATION AGAIN & DECIDED TO PLUG THE WELL SO THEY DUMPED 400 SX THIXOTROPIC CMT DOWN THE 9 5/8", WHICH DISAPPEARED. THEY SPOTTED 2 HOT 75 SX PLUGS AT 290' BUT COULD NOT GET CMT TO THE BOTTOM OF THE 9 5/8". RICHARD LACEY LET THEM SET A CIBP @ 260' & FILL TO SURFACE WITH CMT. I WAS WAITING FOR THEM TO RUN THE 3 STANDS OF DRILL PIPE IN TO PLUG WHEN I REALIZED THEY WERE PUMPING THROUGH A 2" LINE DIRECTLY DOWN THE 9 5/8". HALLIBURTON ONLY PUMPED 17 SX CMT BEFORE CIRCULATING CMT TO SURFACE.

Remarks: USED THIXOTROPIC CMT BY HALLIBURTON ENERGY SERVICES.

Plugged through: CSG

District: 01

Signed *Eric MacLaren*
(TECHNICIAN)

RECEIVED
APR 13 2012
KCC DODGE CITY

✓ 4/30/12
RECEIVED CP-2/3
APR 17 2012
KCC WICHITA *RAWY*