

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00280-00-00  
Spot: NW Sec/Twnshp/Rge: 17-22S-33W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: GARDEN Well #: 1  
County: FINNEY Total Vertical Depth: 2608 feet

Operator License No.: 32864  
Op Name: XTO ENERGY INC.  
Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2457		WITH 5 SX CMT
SURF	8.625	298		WITH 225 SX CMT
PROD	5.5	2584	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2012 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: SAUL NAVARRETE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2486' WITH 5 SX CMT. RTIH TO 2000' WITH 50 SX CMT. PERFORATE @ 1130'. RUN PACKER TO 900'. PUMP 75 SX CMT. TEST TO 500#. IF HOLDS PERFORATE @ 356' WITH 120 SX CMT. CIRCULATE TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/16/2012 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2457' WITH 5 SX CMT. PLUG AT 1984' WITH 50 SX CMT. TOO H W/TBG. PERFORATE @ 1130'. RUN TBG & PACKER TO 917'. BREAK DOWN @ 700#. INJECTION RATE 2 BPM @ 400#. NO BLOW ON THE 5 1/2" X 8 5/8" ANNULUS. PUMP 75 SX CMT OUT PERFS (50 SX OUT & 25 SX INSIDE THE 5 1/2"). TOO H W/TBG & PACKER. WAIT 1 1/2 HOURS. LOAD & TEST 5 1/2" CASING TO 400#. HOLDING. PERFORATE @ 356'. INJECTION RATE 2 BPM @ 50 PSI. CIRCULATE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT WITH 120 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2584	2608	OH	
2547	2560		
2536	2544		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED  
APR 26 2012

KCC WICHITA

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

APR 23 2012

KCC DODGE CITY

4/28/12  
Form CP-2/3

RAWY