

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-20219-00-00  
Spot: NWNW Sec/Twnshp/Rge: 6-22S-2W  
660 feet from N Section Line, 660 feet from W Section Line  
Lease Name: STUCKY-HARMS Well #: 1  
County: HARVEY Total Vertical Depth: 3207 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		220 SXS CMT
PROD	3.5	3206		250 SXS CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2011 12:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: TRAVIS HAMM Company: \_\_\_\_\_ Phone: (620) 755-2744

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: SHANE JONES WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/29/2011 12:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

PULLED 2614' OF 3.5 PREVIOUSLY. RAN 2 3/8 TUBING INTO 2200' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 510' SPOTTED 50 SX OF CEMENT. PULLED TUBING TO 290' - CIRCUALTED TO SURFACE WITH 145 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3142	3182		MISSISSIPPIAN

RECEIVED  
APR 19 2012  
KCC WICHITA

Remarks: CONSOLIDATED CEMENTING OUT OF ELDORADO - 60/40 4% W/ 2% CC. PAST 10 YEAR TA STATUS.

Plugged through: TBG

District: 02

Signed B. J. Hope  
(TECHNICIAN)