

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20214-00-01
Spot: NWSEW Sec/Twnshp/Rge: 1-23S-3W
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: GRABER OWWO Well #: 1
County: HARVEY Total Vertical Depth: 3297 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		175 SX
PROD	4.5	3291	821	125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/28/2011 12:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/02/2011 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED TO 3100' - CAPPED WITH 4 SX, CUT PIPE LOOSE @ 821'. CASING PULLED TO 400' - SPOTTED 150 SX - 3% CC & 150# HULLS TAGGED CEMENT @ 90'. PULLED CASING TO 90' - CIRCULATED WITH 110 SX TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3186	3190		MISSISSIPPIAN

Remarks: COPELAND CEMENT OUT OF BARTON - PAST 10 YEAR - SHUT IN

Plugged through: CSG

RECEIVED
APR 19 2012
KCC WICHITA

District: 02

Signed _____

B. J. Hope

(TECHNICIAN)

✓ 5/07/12

12