

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21271-00-00
Spot: E2NWNENE Sec/Twnshp/Rge: 22-28S-6W
2310 feet from S Section Line, 775 feet from E Section Line
Lease Name: BLANK Well #: 1
County: KINGMAN Total Vertical Depth: 4123 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	304		200 SXS CMT
PROD	4.5	4123	2850	240 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/17/2011 12:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: JAMIE Company: _____ Phone: (620) 755-2744

Proposed
Plugging
Method:

AS PER KCC RULES AND REGULATIONS, AS PER THEIR RECOMMENDATIONS.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 10/19/2011 6:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3069' - CAPPED WITH 4 SX CEMENT. PULLED CASING TO 940'
SPOTTED 35 SX OF CEMENT, TAGGED CEMENT @ 780' 2 HOUR LATER. PULLED
CASING TO 370' CIRCUALTED TO SURFACE WITH 180 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3836	3879		Mississippian

RECEIVED
APR 19 2012
KCC WICHITA

Remarks: COPELAND OUT OF GREAT BEND - 60/40 4% W/3% CC.

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)