

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01150-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 24-30S-8W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: WEST SPIVEY UNIT Well #: 8
County: KINGMAN Total Vertical Depth: 4450 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		250 SX
PROD	5.5	4448		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2011 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC REQUIREMENTS.

Plugging Proposal Received By: JEFF KLOCK

WitnessType: PARTIAL

Date/Time Plugging Completed: 10/17/2011 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4270 - CAPPED WITH 5 SX CEMENT. PERF CASING @ 1250'
SPOTTED 35 SX CEMENT WITH TUBING 2 3/8. PERF CASING @ 700' SPOTTED 35 SX
CEMENT WITH TUBING 2 3/8 @ 260' - PUMPED 55 SX CEMENT DOWN 2 3/8 TUBING,
RAISED CEMENT TO SURFACE - PUMPED 190 SX DOWN 5.5. 10-17-11 TAGGED
CEMENT 620' INSIDE 5.5. 1 INCH DOWN INSIDE 8 5/8 5.5 - CIRCULATED WITH 70
SX OF CEMENT - RAN 2 3/8 TUBING 260' INSIDE 5.5 CIRCULATED TO SURFACE
WITH 75 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4395	4405		
4320	4326		

RECEIVED
APR 19 2012

KCC WICHITA

Remarks: PAST 10 YEAR TA STATUS

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

✓ 5/07/12

1/4