

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20607-00-00
Spot: NENWSEW Sec/Twnshp/Rge: 33-11S-22W
3795 feet from S Section Line, 3465 feet from E Section Line
Lease Name: FLAGLER Well #: 2
County: TREGO Total Vertical Depth: 4080 feet

Operator License No.: 34311
Op Name: JAK OIL LLC
Address: 17050 390TH AVE
ELLIS, KS 67637

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	257		195 SX
PROD	4.5	4065		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2012 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: ROGER L. MOSES Company: PROFESSIONAL PULLING SERVIC Phone: (785) 656-1729

Proposed Plugging Method: Ordered 5 sx gel, 350 sx 60/40 pozmix 4% gel cement, 500# hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2012 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran Tubing to 3830'. Pumped 4 sx gel followed by 50 sx cement w/200# hulls.
Pulled tubing to 2550'. Pumped 85 sx cement w/200# hulls.
Pulled tubing to 1295'. Circulated w/80 sx cement.
POOH. Topped off w/55 sx cement.
Tied onto backside and squeezed w/15 sx cement.
Cement fell back to 250'.
Topped off w/1 3/4 yards ready mix on 4/9/2012.

Perfs:

Top	Bot	Thru	Comments
3988	4002		
3982	3987		

Remarks: QUALITY OILWELL CEMENTING- TICKET # 471

Plugged through: TBG

District: 04

Signed _____

Marvin Mills

(TECHNICIAN)

CM

RECEIVED
APR 19 2012
KCC WICHITA

APR 12 2012

Form CP-2/3

3/07/12