

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19486-00-01
Spot: SWSWNESE Sec/Twnshp/Rge: 3-32S-12E
1567 feet from S Section Line, 1297 feet from E Section Line
Lease Name: MUSTOE Well #: 45A
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	0		
PROD 4		600		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2011 12:00 AM
Plug Co. License No.: 34453 Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION
Proposal Rcvd. from: ANDREW NEGLEY Company: _____ Phone: (620) 431-9500

Proposed Plugging Method: Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill up backside at surface if necessary. Remediate location by removing any surface equipment, fill in pits, cutting off casing 3' below surface and backfill the hole.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/14/2011 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 350' and 150'. Ran 1" to 660' and circulated cement to surface. Pulled 1" and topped well off. A total of 100 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
600	700		

RECEIVED

APR 17 2012 DAS

KCC Chanute Dist. #3

RECEIVED

APR 19 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Duane G Sims

(TECHNICIAN)

3/07/12

Form CP-2/3