

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19488-00-01
Spot: SENESESW Sec/Twnshp/Rge: 3-32S-12E
692 feet from S Section Line, 2819 feet from E Section Line
Lease Name: MUSTOE Well #: 19 A
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	0		
PROD	3	600		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2011 12:00 AM
Plug Co. License No.: 34453 Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION
Proposal Rcvd. from: ANDREW NEGLEY Company: _____ Phone: (620) 431-9500

Proposed Plugging Method: Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill up backside at surface if necessary. Remediate location by removing any surface equipment, fill in pits, cutting casing off 3' below surface and backfill the hole.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 10/24/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 350' and 150'. Ran 1" to 620' and circulated cement to surface. Pulled 1" out of well. Hooked onto 2" and squeezed cement to surface. A total of 120 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
600	700		

RECEIVED
APR 19 2012
KCC WICHITA

RECEIVED
APR 17 2012 DAS
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Duane G. Sims

(TECHNICIAN)