

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19280-00-01
Spot: SENENWSW Sec/Twnshp/Rge: 3-32S-12E
2222 feet from S Section Line, 4061 feet from E Section Line
Lease Name: LONGTON STORAGE Well #: 44A
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/08/2011 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: ANDREW NEGLEY Company: _____ Phone: (620) 431-9500

Proposed Plugging Method: Pull any remaining downhole that has not been cemented. Run pipe to TD. Circulate cement to surface. Trip pipe out. Fill up backside at surface if necessary. Remediate location by removing any surface equipment, fill in pits, cutting casing off 3' below surface and backfill the hole.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 08/08/2011 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 300' and 150'. Ran 1" to 670' and spotted cement that contractor had left. Pulled pipe and went after more cement. Ran back into 450' and hit cement. Circulated cement to surface. Pulled 1" and topped well off. A total of 192 sacks of cement were used to plug this well.

Perfs:

RECEIVED

APR 17 2012 DAS

KCC Chanute Dist. #3


RECEIVED
APR 19 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)