

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20281-00-00  
Spot: W2SWSW Sec/Twnshp/Rge: 12-5S-22W  
660 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ARCHER-NELSON Well #: 5  
County: NORTON Total Vertical Depth: 3544 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		135 SX
PROD	4.5	3543		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/04/2012 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement and 500 # hulls.  
Rods and pump out of hole. Tubing stuck in hole @ 1240.80'  
Top of fish @ 1240.80'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2012 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1240'. Pumped 125 sx cement to circulate to surface.  
Pulled tubing and hooked to 4 1/2" casing. Pumped 125 sx cement w/75 # hulls. Maximum pressure 600 psi. Shut in pressure 200 psi.  
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 50 sx cement. Maximum pressure 200 psi. Shut in pressure 50 psi.

Perfs:

Remarks: SWIFT TICKET # 22378

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

MAY 14 2012

Form CP-2/3

KCC WICHITA

W2SW 05 2012