

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20674-00-00
Spot: SENWNESE Sec/Twnshp/Rge: 12-4S-19W
2030 feet from S Section Line, 930 feet from E Section Line
Lease Name: NORRIS A Well #: 1
County: PHILLIPS Total Vertical Depth: 3487 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/07/2012 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Revd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 05/07/2012 10:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @1575 w/25 sx
2nd plug @936 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

MAY 14 2012

KCC WICHITA

Form CP-2/3

MAY 09 2012