

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20077-00-00
Spot: SESE Sec/Twnshp/Rge: 20-20S-40W
660 feet from S Section Line, 662 feet from E Section Line
Lease Name: PANNING Well #: 1
County: GREELEY Total Vertical Depth: 2855 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2847	0	WITH 200 SX CMT
SURF	8.625	235		WITH 160 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2012 3:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LARRY SPARGER Company: HORSEHOE OPERATING Phone: (432) 683-1448

Proposed Plugging Method: SET CIBP W/2 SX CMT @ 2750' OR 50 SX CMT W/200# HULLS. LOAD CASING WITH WATER & TEST TO 700#. RUN BOND LOG TO DETERMINE TOC. PERFORATE USABLE WATER AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/03/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 75 SX CMT WITH 250# HULLS (2807' TO 1600'). TEST CASING TO 900#. HOLDING. 2/23/12: RAN BOND LOG FROM 2023' TO 150'. POSSIBLE CMT FROM 1670' TO 570' BUT LOGGER IS UNCERTAIN. WELL FILES CONTAIN NO INFO. REGARDING A POSSIBLE CASING LEAK SQUEEZE THROUGH THIS INTERVAL. PERFORATE AT 1310'. INJECTION RATE 2 BPM @ 1300#. SDFN, 2/24/12: INJECTION RATE 1 BPM @ 700# THRU PERFS @ 1310'. PUMP 125 SX CMT (45 SX OUT PERFS) & PRESSURE INCREASED TO 1300#, THEN BROKE BACK. CONTINUE PUMPING & WELL STARTED CIRCULATING. PUMPED TOTAL OF 240 SX (160 SX OUT PERFS) & ANNULUS PLUGGED OFF & PRESSURED TO 1300#. NO CMT TO SURFACE UP ANNULUS. TOC UNKNOWN. LEFT 4 1/2" CASING FULL OF CMT. UNABLE TO PUMP DOWN ANNULUS DUE TO LEAKING BRADEN HEAD. CUT BRADEN OFF & WELD ON PLATE. ATTEMPT TO PUMP DOWN ANNULUS @ 400#. COULD NOT. 4/23/12: RAN 1 1/4" TBG DOWN ANNULUS TO 276'. 5/3/12: CIRCULATED CMT FROM 276' TO 0' USING 80 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2799	2807		


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
MAY 15 2012
KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAY 10 2012
KCC DODGE CITY

Form CP-2/3

5/29/12

DML