

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02065-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 11-10S-20W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: CROFFOOT A Well #: 2
County: ROOKS Total Vertical Depth: 3775 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD. PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3773		
SURF	8.625	197		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2012 9:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: GARY WAGNER Company: QUALITY OIL WELL CEMENTING Phone: (785) 625-6374

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Unable to get tubing out below 2050'.
Perforated @ 1650' and 950'. 2 holes each.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2012 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each @ 1650' and 950'.
Ran tubing to top of fish @ 2050'. Tagged and laid 1 joint down. Quality Oilwell Cementing pumped 150 sx cement. Pulled tubing to 500'. Quality pumped 50 sx cement w/50 # hulls. Circulated cement. Pulled tubing out of hole. Tied on to 5 1/2" casing. Squeezed 5 sx cement @ 600 psi.
Hooked up to backside and pumped 100 sx cement w/ 250 # hulls. Maximum 200 psi. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3773	3775		ARBUCKLE OH
3630	3636		LKC
3557	3562		LKC

Remarks: QUALITY OILWELL CEMENTING TICKET # 412

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

MAY 14 2012

RECEIVED

MAY 16 2012

KCC WICHITA