

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23298-00-01
Spot: NWNWSWSW Sec/Twnshp/Rge: 32-12S-19W
1017 feet from S Section Line, 5031 feet from E Section Line
Lease Name: BAHL Well #: 1
County: ELLIS Total Vertical Depth: 3860 feet

Operator License No.: 31203
Op Name: MCQUADE, OWEN DBA OWEN'S PUMP
Address: 640 E SUNSET AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3851		150 SX
SURF	8.63	212		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2012 10:00 AM
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.
Proposal Revd. from: OWEN MCQUADE Company: OWEN'S PUMPING SERVICE Phone: (785) 483-6321

Proposed Plugging Method: Ordered 300 sx 60/40 pozimix 4% gel cement w/500 # hulls.
DV Tool @ 1514' w/310 sx cement.
Squeezed @ 992' w/220 sx cement on 11/08/2011
Perforations @ 3469' - 3471' (Kansas City); 3760' - 3764' (Marmatin); 3814 - 3822 (Arbuckle)

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2012 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Xtreme Well Service ran in hole with tubing to 3545'. Quality rigged to tubing, mixed and pumped 10 sx gel followed by 75 sx cement w/300 # hulls mixed in.
Pulled tubing to 2050'. Quality rigged to tubing, mixed and pumped 100 sx cement w/100 # hulls mixed in.
Pulled tubing to 1050'. Quality rigged to tubing, mixed and pumped 105 sx cement with 100 # hulls to circulate cement to pit area.
Pulled tubing. Topped off 5 1/2" casing with 15 sx cement. Hole standing full.
8 5/8" casing full of cement on backside.

Perfs:


Top	Bot	Thru	Comments
3814	3822		
3760	3764		
3469	3471		

Remarks: QUALITY OILWELL CEMENTING CO TICKET # 413

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

RECEIVED

MAY 16 2012

Form CP-2/3

KCC WICHITA

MAY 14 2012