

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21796-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 7-20S-9W
342 feet from S Section Line, 2321 feet from E Section Line
Lease Name: CONLEY Well #: 1
County: RICE Total Vertical Depth: 3410 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2382	1482	100 SX
SURF	8.625	215		125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/04/2012 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE Phone: (620) 562-0895

Proposed Plugging Method: PER KCC INSTRUCTIONS.

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 05/04/2012 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS OFF TO 2200' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 1482' AND PULL TO 1250' AND PUMP 50 SX'S CEMENT. PULL CASING TO 850' AND PUMP 35 SX'S CEMENT. PULL CASING TO 265' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED 286 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
2254	2259		CSG

Remarks: 60-40 POZ, 4% GEL, COPELAND TICKET C-37907.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED Form CP-2/3

MAY 16 2012

KCC WICHITA