

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24473-00-00
Spot: NESWNWSW Sec/Twnshp/Rge: 32-16S-11W
1689 feet from S Section Line, 4897 feet from E Section Line
Lease Name: SCHNEWEIS Well #: 1
County: BARTON Total Vertical Depth: 3410 feet

Operator License No.: 7030
Op Name: JOHN ROY EVANS OIL COMPANY LLC
Address: 405 FOURTH ST BOX 385
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3171		90 SX
SURF		475		
SURF	8.625	478		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/14/2012 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GARY KIRMER Company: JOHN ROY EVANS Phone: (620) 793-2026

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2012 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 800' and 475'.
Ran tubing to 3015'. Pumped 125 sx cement w/200 # hulls.
Pulled tubing to 1506'. Pumped 75 sx cement w/100 # hulls.
Pulled tubing to 750'. Circulated cement to surface with 120 sx cement. Circulated up casing.
Shut in casing.
Pumped 10 sx cement. Cement circulated out. Surface pipe shut in.
Pulled tubing. Tied to casing. Topped off w/20 sx cement. Shut in w/150 psi.

Perfs:

Top	Bot	Thru	Comments
3104	3106		
3030	3040		
3000	3006		

RECEIVED
MAY 18 2012
5-18-12
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING

Plugged through: GSG T B G

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

MAY 1 2012