

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25011-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 6-17S-11W
3080 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STEPHEN DEMEL Well #: 1
County: BARTON Total Vertical Depth: 3342 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3332		225 SX CMT.
SURF	8.625	371		225 SX CMT.
TI	2.875	3391		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2012 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO. Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2012 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off Perforations. Topped with 5 sx cement.
Shot off casing at 1443', pulled casing to 1435'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 750'. Pumped 75 sx cement w/100 # hulls.
Pulled casing to 350'. Circulated cement to surface w/ 105 sx cement and 100 # hulls.
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3332	3342		ARBUCKLE OPEN
3060	3133		LANSING
2988	2998		DOUGLAS SAND

RECEIVED
MAY 18 2012
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie *5/22/12*
(TECHNICIAN) CM

MAY 16 2012