

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25557-00-00
Spot: S2SWNWNE Sec/Twnshp/Rge: 3-17S-15W
1250 feet from N Section Line, 2310 feet from E Section Line
Lease Name: D. STEINERT Well #: 2
County: BARTON Total Vertical Depth: 3606 feet

Operator License No.: 33530
Op Name: REIF OIL & GAS COMPANY LLC
Address: PO BOX 298
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3605		200 SX
SURF	8.625	536		215 SX
T1	2.875	0		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2012 9:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: DON REIF Company: REIF OIL & GAS Phone: (620) 653-2976

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2012 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 2425'.
Pulled casing to 1650'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 1050'. Pumped 50 sx cement w/100 # hulls.
Pulled casing to 500'. Circulated cement to surface w/200 sx cement and 100 # hulls.
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3396	3398		
3326	3330		
3135	3148		

RECEIVED
MAY 18 2012
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

MAY 18 2012