

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20377-00-00
Spot: SE Sec/Twnshp/Rge: 1-34S-32W
1361 feet from S Section Line, 1315 feet from E Section Line
Lease Name: RICE DAVIES Well #: 2-1
County: SEWARD Total Vertical Depth: 6300 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6030		
SURF	8.625	1545		WITH 650 SX CMT
PROD	5.5	6300	2006	WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/04/2012 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT 5730'. PLUG AT 1580' WITH 50 SX CMT. PLUG AT 580' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 05/04/2012 3:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

PUMPED 400# HULLS & 25 SX CMT AT 5738'. SDON. TAGGED TOC @ 5760'.
PUMPED 300# HULLS & 25 SX CMT AT 5760'. SHOT 5 1/2" CASING AT 2006'.
CIRCULATED HOLE WITH MUD & PUMPED 50 SX CMT AT 1580'. PUMP 40 SX CMT AT 580'. PUMP 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
5738	5954		

RECEIVED
MAY 18 2012
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Jack Macclashy
(TECHNICIAN)

RECEIVED
MAY - 8 2012
KCC DODGE CITY

BAW