

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22323-00-00  
Spot: SWSWSESW Sec/Twnshp/Rge: 2-30S-4W  
292 feet from S Section Line, 3676 feet from E Section Line  
Lease Name: GADBERRY Well #: 2  
County: SUMNER Total Vertical Depth: 3171 feet

Operator License No.: 7023  
Op Name: KLIMA WELL SERVICE, INC.  
Address: PO BOX 48  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3060		0 SX
SURF	8.625	273		0 SX

Well Type: SWD UIC Docket No: D27606.0 Date/Time to Plug: 05/04/2012 12:30 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: JIM KRAFT Company: KLIMA WELL SERVICE Phone: (620) 793-8888

Proposed Plugging Method: SAND BACK 50' ABOVE CAP WITH 5 SKS CMT. NO RECOVERY. PERF AT 900 & 350'. RUN TUBING TO 900' SPOT 35 SKS. PULL TUBING TO 350 & CIRC CMT.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2012 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE OPEN HOLE WAS FILLED WITH SAND TO 50' AND CAPPED WITH 5 SKS CMT. NO RECOVERY. PERF'D AT 900' & SPOTTED 35 SKS CMT. PERF'D AT 350' AND CIRC'D INSIDE OF 5 1/2" CASING. CLOSE VALVE & PUMP 75 SXS CMT. NO CIRC ON BACKSIDE. WILL CUT OFF AND CHECK FOR SQUEEZE OR RUN 1" TUBING.

Perfs:

Top	Bot	Thru	Comments
3060	3171		

Remarks: COPELAND ACID & CMT COMMON & 60/40 TICKET #39555. TA'D WELL

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

cc to MIC 5/22/12

RECEIVED  
Form CP-2/3

MAY 21 2012

KCC WICHITA