

15-095-30016-0000

Form CP-3
Rev. 6-26-62

16 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Albright "E" Well No. # 1

Location C SW NW Sec. 20 Twp. 29 Rge. 6 (E) (W)

County Kingman Total Depth 4218'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 9:30 PM Day 26th Month April Year 1965

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cement circulated with 160 sacks. Hole
was filled with drilling mud to 215', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 215', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with 2
sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 4/28/65
INV. NO. 1066-11

Signed: Archie Elving
Well Plugging Supervisor