

15-101-20107-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 11 1974  
11-11-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Royalty Well No. A-1

Location CSE-NE Sec. 9 Twp. 14 Rge. (E) (W) 28

County Lane Total Depth 4660'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation,

Address Box #187, Medecine Lodge, Ks. License No. 583

Operation Completed: Hour 12:15 PM Day 2 Month 11 Year 1974

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4325'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to  
4285'. Top of perforations @ 4225'.

Sanded well back to 4200' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing  
(3200') and squeezed well initially with 5 sacks hulls and 25 sacks gel following  
with 150 Cu. Ft. cement. Maximum pump-in pressure-500%. Final Shut-in pressure-200%.  
(Mudding & cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/11/74  
INV. NO. 277-W