

15-101-20109-0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1974  
7-11-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson

Complete Address 408 120 Bldg., Wichita, Kansas

Lease Name Hineman "p" Well No. 1

Location C NW SW Sec. 20 Twp. 19 Rge. (E) (W) 28

County Lane Total Depth 4706'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 6 P Day 8 Month 7 Year 1974

The above well was plugged as follows:

RTD 4706' 8 5/8 csg set at 260' cwc 175 sk. Cmt. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED  
DATE 7/11/74  
INV. NO. 9509-W