

15101-20000000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
4-1-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center, Wichita, Kansas

Lease Name Ware Well No. 3

Location NW NW Sec. 24 Twp. 19 Rge. (E) (W) 28

County Lane Total Depth 4392'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10:30 P Day 27 Month 3 Year 1974

The above well was plugged as follows:

RTD 4392' 8 5/8 csg set at 235' cwc Cem. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk

cem thru drill pipe. Heavy mud to 220' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8856-W