



15-135-20533-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 30 1971
 CONSERVATION DIVISION
 Wichita, Kansas

12-30-1971

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg., Co.

Complete Address: 705 4th Natl. Bk. Bldg., Wichita, Ks.

Lease Name: Stenzel "B" Well No. 1

Location: C SW SE Sec. 6 Twp. 18 Rge. (E)(W) 22

County: Ness Total Depth 4350' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo A. M... ..
 Conservation Division Agent