

State of Kansas



15-135-30199-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1966
04-25-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Miller of Dreiling Dr. Inc. has this
date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: L. J. Dreiling & Sons Inc.

Complete Address: VICTORIA, KANSAS

Lease Name: Schultz Well No. 1

Location: NE-NE Sec. 23 Twp. 18 Rge. 22 (E)(W) X

County Ness Total Depth 4303 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 550 ft.,

and displace 20 sac cement thru drill pipe, heavy mud to 280' set

cementing plug and displace 20 sac cement thru drill pipe, heavy mud

to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing

to base of cellar. Plug rat hole with two sac cement.

Very truly yours,

L. J. Messing
Conservation Division Agent