

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,857 0000

LEASE NAME Honeman

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 26S RGE. 12W (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 2-21-94

Plugging Completed 2-25-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Trans Pacific Oil Corp.

ADDRESS One Main Place, Suite 1000 Wichita, KS 67202

PHONE# (316) 262-3596 OPERATORS LICENSE NO. 9408

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4312'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	328'	none
				5 1/2	4302'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4250' & 5 sks cement. Shot @ 3200, 3000, 2800, pipe came loose. Pulled pipe, put plug container on well. Plugged well down surface casing with 300# hulls, 1000# gel, 50 sks cement, 1000# gel, 100# hulls, plug, mix 175 sks cement, close in head. 60/40 poz 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corp.

MAR 09 1994

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 94

Irene Herzberg
Notary Public

My Commission Expires:

