

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,289 0000

LEASE NAME Hoagland

WELL NUMBER 1-22

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2870 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 22 TWP. 32S RGE. 14 ~~W~~ or (W)

COUNTY Barber

Date Well Completed 12-06-81

Plugging Commenced 12-06-81

Plugging Completed 12-22-88

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, KS 67124

PHONE#(316) 672-7514 OPERATORS LICENSE NO. 5087

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-14-88 (date)

by Paul Luthi (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippi Depth to Top 4642 Bottom 4656 T.D. 5210

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				16	48	None
				8 5/8	885	None
				4 1/2	4843	3757

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged bottom by pumping down 4 1/2" casing as follows: 12 bbls. fresh water with 200# hulls, 25 sxs Class 'A' cement, wiper plug, displaced with 61 bbls. produced water. Pumping pressure vacuum, squeeze pressure 1500#. Top of cement at 3795', pulled 4 1/2" casing. Placed top plugs by pumping down 8 5/8" casing as follows: 9 bbls. fresh water with 300# hulls; 25 bbls. (If additional description is necessary, use BACK of this form.) (OVER)

Name of Plugging Contractor Texas Energies, Inc. License No. 5087

Address P.O. Box 947 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texas Energies, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.


Mark P. Stevenson

(Employee of Operator) or (Owner) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) P.O. Box 947 Pratt, KS 67124



SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 89

Dorothy M. Furgason
Notary Public

My Commission Expires: Feb. 6, 1989

ORIGINAL

0033

fresh water with 10 sxs gel; 50 sxs 60-40 poz mix 6% gel; 3 bbls. fresh water with 100# hulls; 100 sxs 60-40 poz mix 6% gel. Maximum pressure 100#, ISIP 50#, average rate 4 bbls. per minute.

Ran slick line, found top of cement in 8 5/8" casing at 450'. Filled to surface with approximately 6 cubic yards of ready mix cement.

RECEIVED
FEDERAL BUREAU OF INVESTIGATION
U. S. DEPARTMENT OF JUSTICE

APR 1 1968

RECEIVED
FEDERAL BUREAU OF INVESTIGATION
U. S. DEPARTMENT OF JUSTICE

APR 1 1968
FEDERAL BUREAU OF INVESTIGATION
U. S. DEPARTMENT OF JUSTICE