

15-135-22079-co-01

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Ness SEC. 12 TWP. 17 RGE. 26 E/W  
 Location as in quarters or footage from lines:  
 NW/NW/SW


Lease Owner Blue Goose Drilling, Inc.  
 Lease Name Quenzer Well No. #1 (OWWO)  
 Office Address Box 1413 - Great Bend, Ks. 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): D & A  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced April 30, 1983  
 Plugging completed June 8, 1983  
 Reason for abandonment of well or producing formation Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Benny Beck  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4574'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	336'	NONE
				5 1/2"	4561'	3205.71'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 4420' and five (5) sacks cement.  
 Shot pipe @ 3800' and 3200'.  
 Pulled eighty (80) joints 5 1/2" casing.  
 Squeezed well with two (2) sacks hulls, fifteen (15) sacks gel,  
 seventy (70) sacks cement, fifteen (15) sacks gel, one (1) sack  
 hulls, released plug and pumped one hundred (100) sacks 60/40  
 pozmix cement with 2% added gel and 3% calcium chloride.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 20th day of June, 1983



Margaret Prosser  
 Notary Public.

My Commission expires: \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 21 1983

CONSERVATION DIVISION  
 Wichita, Kansas