

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-24063-0000

LEASE NAME Klement

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from ^W Section Line

SEC. 13 TWP. 17 RGE. 26 ^{XX} (E) or (W)

COUNTY Ness

Date Well Completed 10/21/98

Plugging Commenced 10/21/98

Plugging Completed 10/21/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pintail Petroleum, Ltd.

ADDRESS 225 N. Market, Ste 300, Wichita, KS 67202

PHONE#(316) 263-2243 OPERATORS LICENSE NO. 5086

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/21/98 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom 4458 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| Surface | | 208' | 0' | 8-5/8" | 208' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged hole with 205 sacks 60/40 Pozmix, 6% gel, 1/4# Floseal per sack as follows: 50 sx @ 1860', 80 sx @ 1100', 40 sx @ 240', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 3:00 am 10/21/98.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, Ltd.

STATE OF _____ COUNTY OF _____, ss.


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

X (Signature) Walter James Phillips

(Address) 225 N. Market, Wichita KS

X AND SWORN TO before me this 12th day of November, 1998

X Patricia C. Byrle
Notary Public



My Commission Expires: 12/11/2001