

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-22,609-0000

LEASE NAME QUENZER

WELL NUMBER 2-A

SPOT LOCATION SE NE NW

SEC. 13 TWP. 17 RGE. 26 XXXXX (W)

COUNTY NESS

Date Well Completed 8-7-84

Plugging Commenced 8-27-84

Plugging Completed 9-11-84

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AMERICAN PETROLEUM COMPANY, INC.

ADDRESS 400 N. WOODLAWN, SUITE 111 WICHITA, KS. 67208

PHONE # (316) 684-5273 OPERATORS LICENSE NO. 5923

Character of Well OH DH (KCC)  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DISTRICT #1

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing formation NEVER PRODUCED Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPIAN	WATER	4452	4475	8 5/8"	343'	NONE
				4 1/2"	4488'	2250'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. ALL PERFORATIONS OPENED DURING COMPLETION OPERATIONS WERE SQUEEZED EXCEPT PERFORATIONS FROM 4451' TO 4461'. PERFORATIONS FROM 4451' TO 4461' PUMPED 3 SACKS OF HULLS & 10 SACKS OF CEMENT (20 SACKS OF CEMENT REMAINED IN 4 1/2" UP HOLE TO 2250' FROM SURFACE. 9-11-84 PLUGGED WITH 1 HULL, 25 SACKS, 10 GEL AND 125 SACKS OF 60/40 POZ. 2% GEL, & 3% C.C. MAX. PUMPING PRESSURE WAS 200 WITH SHUT IN AT 700#. PLUG DOWN AND JOB COMPLETED AT 3:00 P.M. ON 9-11-84. PLUGGING COMPLETED.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HEMBREE WELL SERVICE (NESS CITY) License No. 960  
 Address 302 E. SYCAMORE, BOX 458, NESS CITY, KANSAS 67560

RECEIVED  
 STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

SEP 13 1984

JAMES T. BARVAIS (employee of operator)   
 of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James T. Barvais

(Address) 400 N. WOODLAWN, SUITE 111 WICHITA, KS. 67208

SUBSCRIBED AND SWORN TO before me this 12 day of SEPT., 1984

Peggy Bennett  
 Notary Public

My Commission expires: 1-22-85



AMERICAN PETROLEUM COMPANY, INC.  
 400 N. WOODLAWN, SUITE 111  
 WICHITA, KANSAS 67208  
 (316) 684-5273

RE: QUENZER 2-A WELL  
 SEC. 13-17S-26W  
 NESS COUNTY, KANSAS

ATTACHMENT "A"

<u>PERFORATIONS</u>	<u>SHOTS PER FOOT</u>	<u>ACIDIZED</u>	<u>SQUEEZED</u>
* 4452' TO 4456'	4 (16)	350 15% MUD ACID WITH 18 GALLONS OF SERVICE SOL, 35# HAMPENE AND 1 GALLON INHIBITOR	
* 4456' TO 4464'	2 (18)	ACIDIZED PER. FROM 4452' TO 4464' WITH 1000 GALLONS 15% MUD ACID WITH 50 GALLONS OF SERVICE SOL AND 1 GALLON OF INHIBITOR	* SQUEEZED PERFORATIONS FROM 4452' TO 4464' & 4471' TO 4475' WITH 100 SACKS OF COMMON.
* 4471' TO 4475'	2 (8)	NO ACID TREATMENT	
** 4470' TO 4475' (RE-PERFORATED)	2 (10)	350 GALLONS OF 15% MUD ACID WITH 18 GALLONS OF SERVICE- SOL & 1 GALLON INH. 35# HAMPENE.	
** 4450' TO 4458' (RE-PERFORATED)	2 (16)	350 GALLONS OF 15% MUD ACID WITH 18 GALLONS OF SERVICE SOL. & 1 GALLON IHN. 35# HAMPENE.	** SQUEEZED PERFORATIONS 4470' TO 4475' AND 4450' TO 4458' WITH 50 SACKS OF COMMON.
4451' TO 4461' (RE-PERFORATED)	2 (20)	750 GALLONS OF MOD 202, 38 GALLONS OF SERVICE SOL. AND 2 GALLONS INHIBITOR	SQUEEZED PERFORATIONS FROM 4451' TO 4461' DURING PLUGGING OPERATIONS. WITH 3 SACKS OF HULLS AND 30 SACKS CEMENT (10 SACKS INTO PERFORATIONS & 20 SACKS REMAINED IN STATE CORPORATION COMMISSION

COMPLETED PLUGGING OF WELL ON 9-11-84 PER ORDERS FROM DISTRICT #1.

SEP 13 1984