

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

15-135-22413-00-00

Form CP-4  
Rev. 12-15-80

AUG 7 6 1983

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ness SEC. 13 TWP. 17S RGE. 26 E/W XX  
Location as in quarters or footage from lines:  
330' FNL x 330' FWL

⊙			
		13	

Locate Well  
correctly on above  
Section Platt.

Lease Owner Anador Resources, Inc.  
Lease Name Quenzer Well No. 1-13  
Office Address 5700 S. Quebec, #320, Englewood, CO 80111  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 8/10/83  
Application for plugging filed Yes  
Plugging commenced 8/10/83  
Plugging completed 1:45 p.m. 8/11/83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Made salt water with trace of oil  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Ruthi  
Producing formation Mississippian Depth to top 4510 bottom 4517 T.D. 4582'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Mississippian	Water	4510	4517	8 5/8" 4 1/2"	300 4581	-0- 2758


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1. Plugged back with sand to 4460' and spotted 4 sx cmt.
2. Freepoint run by Gearhart and had free point at 2758'.
3. Shot pipe off at 2758' and pulled.
4. Plugged surface csg. as follows: 3 1/2 sx hulls  
15 sx gel  
70 sx cmt  
15 sx gel  
1 sx hulls  
All cmt was 50/50/POZMIX 8 5/8" wooden plug  
130 sx cmt to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractors Sun Oilwell Cementing

STATE OF Colorado COUNTY OF Arapahoe, ss.  
Jerry A. Pope (employee of owner) or ~~(owner or operator)~~ of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.



(Signature) Jerry A. Pope  
5700 South Quebec, Suite 320  
Englewood, Colorado 80111

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 83  
Kris Ann Rosengren  
Kris Ann Rosengren  
Notary Public.

My Commission expires: 9/15/84