

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22,302-00-00

LEASE NAME Quenzer

WELL NUMBER 2

660 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 13 TWP. 17 RGE. 26W (E) or (W)

COUNTY Ness

Date Well Completed Spd. 09-28-82

Plugging Commenced 10-22-97

Plugging Completed 10-22-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th Street, Newton, Kansas 67114-8827

PHONE (316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, P&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-22-97 (date)

by Mike Meyer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 4417 Bottom \_\_\_\_\_ T.O. 4430

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	287	0
	Production			5 1/2"	4417	550

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Bottom plug sand and cement to 4365'. Circulated 5 1/2" with fresh water. Allied mixed 140 sacks 60/40 6% gel with 100# hulls, circulated cement. Pulled casing, cellar full. Max pressure 500#. Job started 9:30 am, completed 10:15 am.

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. License No. 6901

Address P. O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Joseph F. Strube

(Address) P. O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 97

Bonnie L. Connell  
Notary Public

My Commission Expires: April 8, 2001  
USE ONLY ONE SIDE OF EACH FORM

