

15-135-19101-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 14 Twp. 17 Rge. 26 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NE SW
Lease Owner Twin Drilling, Inc.
Lease Name Daniels Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-3-65 19____
Plugging completed 12-6-65 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	238'	None
				4-1/2"	4496'	1405'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4505', sanded hole to 4480' and dumped 3 sacks of cement @ 4480' with dump bailer. Pulled 4 1/2" casing, mudded hole to 230', set rock bridge to 220' and dumped 25 sacks of cement @ 220'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1965

CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1965

Milton J. Volin
Notary Public.

My commission expires May 10, 1968

DANIELS #2
Twin Drilling Company, GE. et al.

Total Depth: 4900'
Contractor: Rex & Morris
Commenced: 4-23-63
Completed: 5-1-63

Location: C. NE SW, 14-17S-26W
Hess County, Kansas

Casing Record:
8 5/8 @ 238' w/150 sacks
5 1/2 @ 2496' w/100 sacks

FORMATION	DEPTH
Surface Hole	238
Shale	1030
Shale and Sand	1785
Anhydrite	1865
Shale and Lime	2545
Lime and Shale	3160
Lime	3275
Lime and Shale	3830
Lime	4176
Lime and Shale	4495
Lime	4900

RECEIVED
STATE COMMISSION OF GEOLOGICAL SURVEY
NOV 24 1965
UNIVERSITY OF KANSAS
LAWSON HALL
LANSING, KANSAS

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Koontz
Paul D. Koontz, Geologist

STATE OF KANSAS
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 10th day of May, 1963.

Elizabeth Deschner
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1966.

