

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,165-60-00

LEASE NAME Buxton

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 16 TWP. 17S RGE. 26 ~~XXXX~~ (W)

COUNTY Ness

Date Well Completed 9-11-87

Plugging Commenced 9-11-87

Plugging Completed 9-11-87

LEASE OPERATOR Cross Wind Petroleum / Mid-Continent Energy

ADDRESS 105 S. Broadway, Suite 530, Wichita, KS. 67202

PHONE# (316) 262-5061 OPERATORS LICENSE NO. 4254 / 5205

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #1 - Dodge City

Is ACO-1 filed? will be by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4571'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plug #1 set at 1980' with 50 sacks cement through drill pipe

Plug #2 set at 1090' with 80 sacks cement through drill pipe

Plug #3 set at 260' with 50 sacks cement through drill pipe

Plug #4 set at 40' with 10 sacks cement 15 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address PO Box 877, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) PO Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 16 day of September, 1987

RECEIVED  
STATE CORPORATION COMMISSION  
Dorothy M. Hague  
Notary Public



Expires: \_\_\_\_\_  
SEP 17 1987

DRILLERS WELL LOG

DATE COMMENCED: September 5, 1987  
 DATE COMPLETED: September 11, 1987

CrossWind Petroleum/  
 Mid-Continent Energy  
 Buxton #1  
 NE/4, NW/4  
 Sec. 16, T17S, R26W  
 Ness County, KS

0 - 1940 Surface Soil, Shale, Sand  
 1940 - 1980 Anhydrite  
 1980 - 3849 Shale, Lime  
 3849 - 3854 Shale  
 3854 - 3870 Lime, Shale  
 3870 - 4198 Lime  
 4198 - 4328 Shale, Chert, Lime  
 4328 - 4399 Lime, Chert  
 4399 - 4507 Lime  
 4507 - 4571 Chert, Lime  
 4571 RTD

ELEVATION: 2566' K.B.

FORMATION DATA

Anhydrite	1940-1980
Heebner	3849
Toronto	3870
Kansas City	3891
Base K.C.	4198
Marmaton	4238
Pawnee	4328
Fort Scott	4399
Mississippi	4507
RTD	4571

Surface Pipe: Set new 8-5/8" pipe at 218' with 140 sacks 60/40 pozmix, 2% gel, 3% c.c.

A F F I D A V I T


STATE OF KANSAS  
 COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*  
 Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 16 day of September, 1987.

*Dorothy M Hague*  
 Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 17 1987  
 CONSERVATION DIVISION  
 Wichita, Kansas