

15-135-28734-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Norton Well No. 1

Location NE SE Sec. 23 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4424'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn Pipe Pulling Company

Address Box 156 Ellinwood, Kansas 67526 License No. 686

Operation Completed: Hour 5.30 P Day 11 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 4424' 8 5/8 csg set at 303' cwc 175 sk.

5 1/2 csg set at 4411' cw 175 sk cmt.

Set 5 1/2 plug at 4380' & dumped 5 sk cmt W/dump bailer. (4345-4380)

Cutoff and recovered 3318' Of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls -70 sk cmt -10 sk gel &

water -released 8 5/8 plug and pumped 50 sk cmt. PP 800 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 6/4/73

INV. NO. 9450-42