

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson
Complete Address 408 One-Twenty Bldg., Wichita, Kansas
Lease Name Combest "A" Well No. 1
Location C SW NE Sec. 26 Twp. 17 Rge. (E) (W) 26
County Ness Total Depth 4460'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 9:30 A Day 9 Month 5 Year 1974

The above well was plugged as follows:

RTD 4460' 8 5/8 csg set at 256' cwc 180 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. F. Massey
Well Plugging Supervisor

INVOICED

DATE 5/15/74
INV. NO. 9114-W