

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1978

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 21,479 - 0000 (of this well)

Operator's Full Name Euwer Petroleum Co., Inc. & Rains & Williamson Oil Co., Inc.

Complete Address Suite 206, Litwin Bldg, 110 N. Market, Wichita, Kansas

Lease Name Solze Well No. 1

Location SE NE SE Sec. 28 Twp. 17 Rge. (E) (W) 26

County Neosho Total Depth 4432'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Buffalo Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 9 P Day 17 Month 6 Year 1978

The above well was plugged as follows:

RTD 4432' 8 5/8 csg.set 281' cwc 180 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cem plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messer  
Well Plugging Supervisor

DATE 6-20-78

INV. NO. 7521-W