

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-44

LOCATION C 11E-11E

SEC. 28 TWP. 17 RGE. 26-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Scott-Solpe

Operator W. W. L. Hartman Address Box #64 Wichita-Kans.

Field _____ County Ness

Total Depth 4318 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13 3/8 - 120 ft. Circulated with cement
5 1/2 casing set at 4437 ft - 50 sacks of cement.
Plugged back to 4300 ft. with cement & rock.
Dumped 5 sacks of cement at 4300 ft - Shot off 2 -
hulled the 5 1/2 casing - mud to 140 ft - Set 10 ft. Rock Bridge
to 30 sacks of cement at 140 ft - mud to 15 ft. Bridge
to 10 sacks of cement at the surface -
A. & S. Pipe Pulling Co. - Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1952

CONSERVATION DIVISION
Wichita, Kansas

C. W. Stough -
District Conservation Agent

Date 1-7-52

PLUGGING
FILE SEC 28 TWP 17 R 26
BOOK PAGE 125 LINE 44